

Parking Access Aisles and Accessible Routes



Accessibility Code


Building Code

Exterior

ADA

Design Development

Construction Docs



Overview

Accessible routes must connect directly to access aisles. Curb ramps, where provided, cannot protrude into access aisles (which cannot slope more than 1:48 max.) to accommodate wheelchair transfers and vehicle ramps or lifts (section 502.4). A landing at least 36" deep is required at the top of curb ramps; in alterations where space for this landing is unavailable, curb ramps must have side flares with a 1:12 max. slope (section 406.4).

Primary Sections

ADA 406.4 Landings ('10)

